

GCC LLC

Division 27 & 28 Low-Voltage Contractor • KCMO / STL

PROPOSAL FOR

Parkway North High School — Summer 2027 Low-Voltage Refresh

Prepared for:	Meyer Construction
Attn:	Mike Reynolds, Senior Estimator
Date:	2026-04-21
Valid through:	2026-06-20
Our reference:	GCC-2026-0412

01 — Cover Letter

Mike,

Thanks for sending over the RFP (MC-2027-014, issued 2026-04-02) for the Parkway North summer refresh. We've walked similar K-12 summer windows at Liberty Middle and Francis Howell Central — the hard constraint is always the same: every classroom has to come back online before teachers re-enter for in-service, and every cable has to test green the first time because nobody gets to come back in August for a second pass.

We're proposing a fully-certified Cat6A structured cabling rebuild across the three academic wings, an IP camera refresh covering the 47 new and relocated positions, and a reworked telecom room with a 48-port PoE+ aggregation. Every cable will be Fluke DSX-8000 certified with a LinkWare PDF delivered on closeout, every pathway will be TIA-569-E compliant, and every cross-connect will carry a TIA-606-C label that your FM staff can trace without a ladder.

This proposal is valid for 60 days, our bond capacity through AmGUARD covers the full scope, and the schedule below mobilizes the Monday after graduation weekend with substantial completion two weeks ahead of the first in-service day.

Kaitlyn Lim Morris President & CEO GCC LLC (636) 224-8192 · corporate@greencommllc.com

02 — Bid Overview

Project: Parkway North High School — Summer 2027 Refresh

Base Bid: \$387,400

Alternate	Amount
A1 — Managed Services (month-to-month)	\$1,850 / month
D1 — Weekend / After-hours DEDUCT	-\$8,200
Loyalty Discount (if applicable)	-\$19,370
Net Bid (after Loyalty)	\$368,030

Schedule: Mobilize Mon 2027-05-31; substantial completion Fri 2027-07-30.

- Every cable Fluke DSX-8000 certified with a LinkWare PDF on closeout
- Cat6A plenum baseline — no Cat6 substitutions, period
- Lifetime workmanship warranty that transfers with the property
- We have never missed a project completion date

03 — Scope of Work

3.1 Base Scope — Structured Cabling

GCC will furnish and install a new Cat6A plenum-rated structured cabling system across the three academic wings (A, B, C) and the field house annex. Installation follows TIA/EIA-568-D commercial building cabling standards and NEC Articles 725 and 800.

Inclusions:

- 420 Cat6A plenum data drops — classroom, office, AP coverage, WAP, and POS locations
- All drops home-run to the second-floor IDF via existing J-hook pathway, supplemented where required
- Termination on new Leviton Atlas-X1 24-port patch panels in the IDF
- Room-end termination on Leviton QuickPort Cat6A keystones in single-gang decora plates
- Full Fluke DSX-8000 Cat6A permanent-link certification for every drop
- TIA-606-C labeling: every cable, every jack, every patch-panel port
- LinkWare PDF test report delivered as part of closeout

3.2 Base Scope — Electronic Security

GCC will furnish and install an IP video surveillance expansion covering interior and exterior coverage per the architect's security diagram dated 2026-03-14.

Inclusions:

- 47 IP camera installations — mix of interior dome, exterior bullet, and parking-lot vari-focal
- Hikvision DS-2CD series cameras per spec (OFCI — GCC installs only)
- Cat6A PoE++ homeruns to the new Ubiquiti UniFi Pro Max 48 PoE aggregation switch
- Cable tray and J-hook pathway supplement where the existing infrastructure is undersized
- NVR integration — GCC coordinates with District IT; NVR is OFCI
- 18 access-controlled door positions — reader, REX, door contact, strike tie-in — terminating at a new Mercury Security LP1502 board in the IDF

3.3 Base Scope — Telecom Room

Inclusions:

- One new 42U free-standing rack, seismic-bolted, in the second-floor IDF
- Ladder rack from the rack to the existing cable-tray pathway
- New 48-port Ubiquiti UniFi Pro Max 48 PoE aggregation switch (furnished by GCC, wired by GCC)
- Copper patch field for the 420 data drops
- Power strip (PDU) — 20A, 16-outlet, surge-protected
- TIA-606-C labeling throughout the rack
- Rack elevation drawing delivered as part of closeout

3.4 Base Scope Summary

Item	Quantity	Unit
Cat6A plenum data drops	420	each
IP camera installs	47	each
Access-controlled door positions	18	each
Fiber backbone strands (existing — retained)	24	strand
New 42U rack	1	each
48-port PoE aggregation switch	1	each

3.5 Exclusions

The following scope items are excluded from this bid and are the responsibility of others:

- Fire alarm systems and all Division 28 life-safety
- Nurse-call systems
- Classroom audiovisual equipment (projectors, displays, ClearTouch boards) — OFCI installation only on request
- Building controls, HVAC controls, lighting controls
- Core drilling beyond what is shown on the architect's drawings
- Drywall patching, paint, and finish carpentry
- Asbestos abatement, lead abatement, or any hazardous-material work
- Temporary cabling or service continuity during construction — this is a dark-site refresh
- Permits beyond low-voltage; the GC carries the base building permit
- Any scope item not explicitly listed above

04 — About GCC

GCC LLC is a Division 27 and Division 28 low-voltage contractor serving the Kansas City and St. Louis metros. Our work covers structured cabling, electronic security, access control, IP video, audiovisual, paging, and telecom room buildout across commercial new construction, commercial renovation, K-12, healthcare, and residential custom work.

We are privately held, based in St. Peters, Missouri, and licensed to work across Missouri and Kansas. Our field crews carry BICSI TDDMM credentials, OSHA 10 and OSHA 30 certifications, and Hilti PAT licensing for powder-actuated tool use. Every project is PM'd by an in-house Project Manager or RCDD — we do not sub out our supervision.

Every cable we install is Cat6A plenum-rated. Every certification is delivered in LinkWare PDF form, not a line item on a checklist. Every cross-connect is TIA-606-C labeled.

05 — Qualifications

Team. Kaitlyn Lim Morris serves as President and CEO. Nathan Morris leads operations and estimating. Dustin Morris leads field delivery. Taylor Morris manages finance and administration. All four are directly reachable by any GC PM during any active project.

Insurance & Bonding.

Coverage	Carrier	Limit
General Liability	Next Insurance	\$2M aggregate
Workers' Comp	AmGUARD (policy GRWC763142)	Statutory
Auto	Next Insurance	\$1M combined single
Bond Capacity	Via AmGUARD	\$5M single / \$15M aggregate

Certifications. BICSI TDMM, Leviton Atlas-X1 certified installer, Ubiquiti UniFi Enterprise, Hikvision certified, Mercury Security authorized integrator, OSHA 10 and OSHA 30 for every field staff member.

Testing Equipment — owned in-house.

- Fluke Networks DSX-8000 Cat6A CableAnalyzer — primary certification tool
- Fluke OptiFiber Pro OTDR — fiber backbone certification
- Fluke LSPM light source and power meter — optical loss testing
- Brady M611 labeler for TIA-606-C compliant labels

Prior Work References.

- **Francis Howell Central — 2024 Summer Refresh.** 380 Cat6A drops, 42 cameras, 14-week summer window. GC: Paric Corporation. Delivered two weeks early; zero callbacks.
- **Liberty Middle School — 2025 New Construction.** 520 Cat6A drops, 38 cameras, 22 access-controlled doors, full MDF/IDF buildout. GC: McCarthy Building Companies.
- **St. Charles County Ambulance District HQ — 2025.** Occupied-space refresh with ICRA-adjacent infection-control adjacent to the 911 dispatch floor. GC: S.M. Wilson.

Reference contacts available on request.

06 — Warranty

LIFETIME WORKMANSHIP WARRANTY

Every termination, every splice, every pathway install — covered for as long as the cable is in service, and the warranty transfers to the next property owner at no cost. If a cable we installed gives you trouble in 2031, we come back. If the building sells, the next owner has the same coverage we extended on day one.

Equipment carries its own manufacturer warranty. GCC-furnished hardware is covered for five years of advance replacement.

07 — Project Management & Delivery

GCC assigns a dedicated Project Manager and RCDD to every commercial project. Our PM attends all OAC meetings, issues weekly status updates, and holds a standing coordination call with the GC's site PM.

Two-person crew minimum on site at all times — never a single tech. One foreman per three field staff. Every crew member is OSHA-30 certified and carries the site-safety certifications required by the owner and the GC.

Site conduct: uniformed crew, badged, clean vehicle, clean jobsite at end of every shift. No smoking on campus. No profanity in classroom-adjacent areas.

08 — Schedule

1. Week 1 (2027-05-31): Mobilize, secure IDF, stage material.
2. Weeks 2–4 (2027-06-07 to 06-25): Rough-in pathway and cable pull, three academic wings.
3. Weeks 5–6 (2027-06-28 to 07-09): Termination and rack buildout.
4. Week 7 (2027-07-12 to 07-16): Fluke DSX-8000 certification sweep; punch.
5. Week 8 (2027-07-19 to 07-23): IP camera install, access-control tie-in, system test.
6. Week 9 (2027-07-26 to 07-30): Closeout — LinkWare PDF, rack elevations, TIA-606-C label schedule, owner walkthrough.

Schedule Notes. Building is dark starting graduation weekend (2027-05-29). In-service begins 2027-08-09; our substantial completion of 2027-07-30 leaves a 10-business-day cushion. Weekend work is not required for the base bid. Alternate D1 (weekend / after-hours DEDUCT) reflects a scenario where the district wants to accelerate by having us give up Saturday overtime and instead work a compressed 4-day week.

09 — Investment Summary

Category	Amount
Base Bid	\$387,400
Alternate A1 — Managed Services (month-to-month)	\$1,850 / month
Alternate D1 — Weekend / After-hours DEDUCT	-\$8,200
Loyalty Discount (5% future + 5% active MS)	-\$19,370
Net Bid (after Loyalty)	\$368,030

Payment terms. Progress billing monthly, net-30. 10% retention held until closeout package is accepted. No deposit required on work under \$500K; mobilization invoiced at first monthly draw.

10 — Terms & Conditions

- 1. Acceptance.** This proposal becomes a binding contract upon written acceptance or upon GCC's receipt of a purchase order referencing this proposal.
- 2. Scope.** Work includes only the items listed in Section 03 (Scope of Work) of this proposal. Items in Section 3.5 (Exclusions) are expressly excluded.
- 3. Changes.** Any change to the scope of work will be documented on a written Change Order signed by both parties before the work is performed. Change Order pricing applies a 10% markup over direct cost.
- 4. Schedule.** Dates in Section 08 assume timely material delivery, site access per the GC's coordination schedule, and dry site conditions. Delays caused by others that push GCC's work outside the contracted window entitle GCC to an equitable adjustment of price and schedule.
- 5. Price & Payment.** Price is firm through the validity date on the cover page. Progress billing monthly, net-30. Late payment accrues interest at 1.5% per month. Mechanic's lien rights are preserved under Missouri RSMo Chapter 429.
- 6. Lien & Waiver.** GCC furnishes conditional lien waivers with each monthly draw and unconditional lien waivers following payment clearance.
- 7. Warranty.** GCC warrants workmanship for the life of the cable (see Section 06). Equipment carries its manufacturer warranty. GCC is not responsible for defects caused by others, by building settlement, by acts of nature, or by unauthorized modification.
- 8. Insurance.** Coverage per Section 05. Certificates of insurance furnished on request. The GC is named as additional insured on the general liability policy.
- 9. Exclusions.** See Section 3.5.
- 10. Termination.** Either party may terminate for material breach uncured 10 days after written notice. If the GC terminates for convenience, GCC is paid for work performed plus a 10% termination fee on the unearned balance.
- 11. Dispute Resolution.** Disputes are submitted first to good-faith negotiation, then to binding arbitration under AAA Construction Industry Rules in St. Charles County, Missouri.
- 12. Safety.** GCC complies with OSHA and site-specific safety programs. Two-person minimum on site. OSHA-30 for foremen; OSHA-10 minimum for all field staff.
- 13. Miscellaneous.** This proposal is governed by Missouri law. Venue is St. Charles County. No oral modifications. Severability applies — one invalid clause does not invalidate the rest.

11 — Acceptance

By signing below, Meyer Construction accepts GCC LLC's proposal for Parkway North High School — Summer 2027 Low-Voltage Refresh at the Base Bid of \$387,400, subject to the terms and conditions herein.

Signature: _____

Name: _____

Title: _____

Date: _____