



Quality Assurance / Quality Control (QA-QC) Plan

Green Communications Contracting LLC · Effective April 9, 2026

1. Quality Policy

We deliver every project to specification, on schedule, with zero defects at final inspection. Quality is built into every phase of our work — from material procurement through final certification testing.

2. Applicable Standards

- ANSI/TIA-568.2-D (Balanced Twisted-Pair Cabling)
- ANSI/TIA-568.3-D (Optical Fiber Cabling)
- ANSI/TIA-606-C (Administration Standard for Telecommunications Infrastructure)
- BICSI TDMM 15th Edition
- NEC / NFPA 70 (as applicable to low-voltage)
- OSHA 29 CFR 1926 (Construction Safety)
- Project-specific specifications and drawings

3. QA/QC Responsibilities

Role	Responsibility
QA Manager (Nathan Morris)	Oversees quality program, conducts inspections, reviews test results, approves corrective actions
Field Installers	Follow installation standards, perform self-inspections, report deficiencies
CEO (Kaitlyn Morris)	Reviews quality metrics, approves program updates

4. Pre-Installation QC

Before we begin installation on any project, we complete the following:

- Review all project drawings, specifications, and addenda.
- Verify material approvals are complete.
- Confirm cable and connector types match the spec.
- Inspect all materials upon delivery for damage and correct part numbers.
- Conduct a site walk to verify pathway routing and TR locations match drawings.
- Brief the crew on project-specific quality requirements.

5. Installation QC

During installation, we maintain quality through:

- Cable handling — We maintain bend radius per manufacturer specs, do not exceed pulling tension limits, and protect all cable from damage.
- Termination — We terminate all copper to T568B (unless spec requires T568A) and maintain pair twist to within 0.5" of termination point.
- Fiber — We clean and inspect all connectors before mating; we fusion-splice per manufacturer procedures.
- Pathway — We install J-hooks at maximum 48" intervals, maintain cable fill ratios per NEC, and separate low-voltage from power per code.
- Labeling — We label both ends of every cable per ANSI/TIA-606-C before testing.
- Daily inspection — Our field supervisor inspects all work completed each day and corrects deficiencies before proceeding.

6. Testing & Certification

- We test 100% of all copper links using Fluke DSX-8000.
- We test 100% of all fiber links using Fluke CertiFiber Pro.
- We test to the permanent link model for copper and the channel model when required.
- Every link must pass — we do not sample.
- Failed links are re-terminated and re-tested until they pass.
- We export all test results via Fluke LinkWare and deliver PDF + .flw files.

7. Labeling Standards

- We follow ANSI/TIA-606-C at both ends of every cable.
- Cable IDs match the cable schedule and as-built documentation.
- We use machine-printed labels (no handwriting).
- Labels are applied to cables, patch panels, faceplates, and racks.



8. Security / Access Control QC (Division 28)

- We verify all reader, camera, and contact locations match drawings before rough-in.
- We confirm cable types match spec (shielded where required).
- We test continuity on all security cabling before device installation.
- We coordinate with the security integrator for device programming and commissioning (programming is by others).

9. Closeout Documentation

At project completion, we deliver:

- 100% Fluke test results (PDF + LinkWare)
- As-built cable schedule with actual measured lengths
- As-built rack elevation drawings
- Label matrix
- Product data sheets and manufacturer warranty certificates
- O&M manual

10. Non-Conformance & Corrective Action

When we identify a deficiency:

- We document the issue (location, description, root cause).
- We implement corrective action immediately.
- We re-inspect and re-test after correction.
- We record the resolution in our project quality log.
- We review recurring issues at the end of each project to update our procedures.

Prepared by: GCC Estimating Department · Contact: kaitlyn@greencommllc.com · (636) 224-8192