



CABLE SCHEDULE

{{JOB NAME}} — {{GC NAME}} — {{SITE CITY, STATE}}

INTERNAL DOCUMENT — GCC EYES ONLY

Contains internal cost rates, margin analysis, and strategy. Never attach to a proposal, quote, or email to a GC, Owner, or Subcontractor.

PURPOSE

Single source of truth for field crew on every cable installed on this job. Captures site-wide cable spec, color discipline, service loops, wall plates, TR/IDF/MDF buildouts, and LF totals. Reconciles with BTQ quantities and Drop Counts. Updated through bid + construction.



1. Site-Wide Cable Spec

Discipline	Cable	Jacket Color	Connector	Test Class
Data (horizontal)	Cat6A plenum (GCC baseline — never Cat6)	Blue	RJ-45 8P8C	Class EA
Voice (horizontal)	Cat6A plenum	White	RJ-45 8P8C	Class EA
CCTV	Cat6A plenum	Green	RJ-45 / BNC where analog	Class EA
ACS (readers, REX, door contacts)	Cat6A plenum + 22/4 comp	Red	Termination per mfr	Continuity + polarity
Intercom / paging	Cat6A plenum	{{per spec}}	RJ-45	Class EA
Fiber backbone	OS2 SM 12-strand (min)	Yellow	LC / SC fusion	OTDR bidir + insertion
Fiber horizontal (fiber-to-desk)	OM4 MM 2-strand	Aqua	LC fusion	OTDR + insertion
Coax (AV / CATV feeds)	RG-6 quad-shield plenum	Black	F-type compression	DC continuity

Included Upgrades (GCC baseline on every bid)

- Cat6A plenum on every data drop — included at no upcharge to the GC, even when the base spec calls for Cat6. Cat6 substitute for Cat6A is NEVER offered.
- TIA-606-C Class 3 labeling on both ends of every cable.
- Fluke DSX-8000 Class EA certification on every Cat6A drop. LinkWare PDF at closeout.
- Lifetime GCC workmanship warranty on every cable.



2. Service Loops & Slack

Location	Service Loop Length	Coiled / Routed
MDF (head-end)	10 ft	Coiled above rack, velcro-bound
IDF (intermediate)	10 ft	Coiled above rack, velcro-bound
Endpoint (WAP, camera, wall plate)	3 ft	Looped above ceiling tile
Elevator shaft (per cab)	5 ft at MDF + 5 ft at cab	Coiled, secured with zip ties (no tape)
Roof-top camera / device	6 ft	Inside pathway before roof penetration

Service loops are non-negotiable minimums. When pathway doesn't allow, crew documents deviation on the as-built. Never cut below these lengths.



3. Wall Plates & Connectors

Location Type	Plate Style	Port Count	Labels
Workstation	Single-gang flush, white	2 (1 blue data, 1 white voice)	Room-port format per TIA-606-C
WAP	Ceiling mount (if exposed); above-tile flush (standard)	1 (blue data)	WAP-# label on cable + plate
Camera drop	Ceiling mount if exposed; plate above tile	1 (green CCTV)	CAM-# label
ACS reader	Single-gang, color per finish schedule	1 (red ACS + 22/4)	DR-# label
Conference room	Single-gang flush, white	{ {spec count} }	Room-port
Kiosk / wall display	Single-gang flush, white	1 (blue data)	KIOSK-#



4. TR / IDF / MDF Buildouts

MDF (head-end)

- 42U floor-standing rack (or as specified) — ladder rack overhead, vertical cable managers both sides.
- 3/4" fire-treated plywood backboard, painted dove-gray, floor-to-ceiling wall.
- #6 AWG grounding buss bar at 18" AFF, tied to building ground electrode (verify with EC).
- Horizontal patch panels: 48-port Cat6A, 1U each, populated per drop count.
- Fiber housing: 4U LIU/FDF with LC couplers, populated per backbone strand count.
- PDU: 20A L5-20R, minimum 2 per rack (A+B feed if redundant power available).
- UPS: sized per active-equipment load (sized at closeout, not base bid).

IDF (intermediate)

- Wall-mount rack (typ.) or 42U floor-standing (on spec).
- Plywood backboard, buss bar, PDU — same spec as MDF.
- Fiber backbone termination: LIU sized to strand count + 100% spare capacity.
- Horizontal patch panels sized to drop count per closet.

Cable management

- Vertical managers both sides of rack.
- Horizontal manager 1U between every patch panel.
- Velcro bundles only — no zip ties on horizontal cable in rack.
- Service loops dressed overhead, coiled, velcro-bound.



5. Cable LF Totals

Cable Type	Drops / Strands	Avg Run	Waste %	Total LF	Boxes / Reels
Cat6A plenum (data)	{{ }}	{{ avg }} ft	10%	{{ }}	{{ }}
Cat6A plenum (voice)	{{ }}	{{ avg }} ft	10%	{{ }}	{{ }}
Cat6A plenum (CCTV)	{{ }}	{{ avg }} ft	10%	{{ }}	{{ }}
Cat6A plenum (ACS)	{{ }}	{{ avg }} ft	10%	{{ }}	{{ }}
Fiber OS2 SM backbone	{{ }}	{{ }} ft	5%	{{ }}	{{ }}
22/4 composite (ACS)	{{ }}	{{ }} ft	10%	{{ }}	{{ }}
RG-6 plenum coax	{{ }}	{{ }} ft	10%	{{ }}	{{ }}

Box count: $[total\ LF / 1000] \times 1.05$ (5% safety stock per Conservative Labor Rule). Fiber reel count: round up to next standard reel length carried by supplier.



6. Field Rules (for installers)

- No cable touches a ceiling tile, pipe, sprinkler, or lighting fixture. All supported by J-hook, cable tray, or EMT.
- J-hook spacing: max 4 ft center-to-center above accessible ceiling.
- Bend radius: Cat6A = 4× cable OD minimum (typically 1"); fiber = 10× cable OD minimum.
- Pull tension: Cat6A max 25 lbf; fiber max 600 lbf (long-term), 200 lbf (pull).
- Firestop: installed by others (GCC does not carry firestop in base bid — see Bid Proposal §7.C).
- Labels: printed (Brother P-touch or equivalent) — hand-written labels never accepted at closeout.
- Every cable tested at termination; fails get reworked on the spot, not deferred.
- Daily close-out: crew logs installed cable count + location in Field Guide.



7. Reconciliation Sources

- Drop counts: `{{Job}}/Internal/Drop Counts.pdf`
- BTQ quantities: `{{Job}}/Internal/BTQ.xlsx` — cable subtotal must match \$5 total LF.
- Labor Plan: `{{Job}}/Internal/Labor Plan.xlsx` — per-drop hours reconcile with Master Catalog Services sheet.
- Field Guide: `{{Job}}/Internal/Field Guide.pdf` — installer's floor-by-floor checklist reads from this doc.